

GENERAL SUMMARY

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150

Project ID: 1005-26

Scope: GC



BUILDING GSF		6,383		
DIVISION NO.		DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
1000	GENERAL REQUIREMENT		\$ 53,600	\$ 8.40
3000	CONCRETE		\$ 117,911	\$ 18.47
4000	MASONRY		\$ 842	\$ 0.13
6000	WOOD, PLASTIC & COMPONENTS		\$ 16,263	\$ 2.55
7000	THERMAL AND MOISTURE PROTECTION		\$ 95,925	\$ 15.03
8000	OPENINGS		\$ 50,432	\$ 7.90
9000	FINISHES		\$ 144,810	\$ 22.69
10000	SPECIALITIES		\$ 12,374	\$ 1.94
11000	EQUIPMENTS		\$ 294	\$ 0.05
12000	FURNISHING		\$ 7,338	\$ 1.15
13000	SPECIAL CONSTRUCTION		\$ 348,921	\$ 54.66
21000	FIRE SUPPRESSION		\$ 8,798	\$ 1.38
22000	PLUMBING		\$ 37,084	\$ 5.81
23000	HVAC		\$ 98,364	\$ 15.41
26000	ELECTRICAL		\$ 63,669	\$ 9.97
28000	ELECTRONIC SAFETY AND SECURITY		\$ 9,640	\$ 1.51
32000	EXTERIOR IMPROVEMENTS		\$ 40,609	\$ 6.36
TOTAL TRADE COST			\$ 1,106,874	\$ 173
OVERHEAD AND PROFIT		15%	\$ 166,031.06	\$ 26.01
INSURANCE		2%	\$ 16,603	\$ 2.60
CONTINGENCY		0%	\$ -	\$ -
TAX		5%	\$ 49,809	\$ 7.80
SUGGESTED BID			\$ 1,339,317	\$ 209.83

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
Project ID: 1005-26
Scope: GC



Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS													
1			Permits	LS	1	0%	1	40.000	\$ 40.00	\$ 1,600.00	\$ -	\$ 1,600.00	\$ 1,600
2			Supervision and Coordination	LS	1	0%	1	450.000	\$ 40.00	\$ 18,000.00	\$ -	\$ 18,000.00	\$ 18,000
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ 40.00	\$ -	\$ -	\$ -	\$ -
4			Final Cleaning	LS	1	0%	1	75.000	\$ 40.00	\$ 3,000.00	\$ -	\$ 3,000.00	\$ 3,000
5			Mobilization Costs	LS	1	0%	1	250.000	\$ 40.00	\$ 10,000.00	\$ -	\$ 10,000.00	\$ 10,000
6			Temporary Control & Facilities	LS	1	0%	1	350.000	\$ 40.00	\$ 14,000.00	\$ -	\$ 14,000.00	\$ 14,000
7			Scaffolding	LS	1	0%	1	175.000	\$ 40.00	\$ 7,000.00	\$ -	\$ 7,000.00	\$ 7,000
												SUBTOTAL	\$ 53,600

CONCRETE

			FOOTINGS											
			DRILLED PIER											
8	S1.0, S1.2	Plan Notes	1'-6" Dia Concrete Pier	CY	6	10%	6	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 2,347	
9			#3 Ties @ 18" O.C	LBS	121	10%	133	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 224	
10			4#5 Vertical Bar	LBS	375	10%	413	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 695	
11			2#5 Vertical Bar	LBS	250	10%	275	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 464	
12			2'-0" Dia Concrete Pier	CY	3	10%	3	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 1,113	
13			#3 Ties @ 18" O.C	LBS	44	10%	48	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 82	
14			5#5 Vertical Bar	LBS	125	10%	138	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 232	
15			2#5 Vertical Bar	LBS	33	10%	37	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 62	
					DRILLED PIER CAP									
16			(3'-0" W x 2'-6" H) Pier Cap	CY	15	10%	16	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 5,866	
17			7#5 Bars @ Top, Bottom, Middle	LBS	387	10%	426	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 717	
18			3#5 Bar @ 2'-0"	LBS	86	10%	95	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 159	
19			#3 Bar Stirrups @ 36" O.C	LBS	73	10%	80	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 135	
20			#3 Single Leg Stirrups @ 36" O.C	LBS	19	10%	20	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 34	
21			(3'-0") 6 Mil. Vapor Barrier	SF	159	10%	175	0.002	\$ 46.90	\$ 0.09	\$ 0.23	\$ 0.32	\$ 57	
					GRADE BEAM									
22			(1'-6" H x 0'-10" W) Concrete Beam	CY	24	10%	26	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 9,404	
23			4#4 Bars	LBS	1363	10%	1499	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 2,523	
24			#3 Bar Stirrups @ 36" O.C	LBS	257	10%	283	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 476	
25			(3'-9") 6 Mil. Vapor Barrier	SF	1912	10%	2104	0.002	\$ 46.90	\$ 0.09	\$ 0.23	\$ 0.32	\$ 681	
26			(1'-2" W x 2'-6" H) Concrete Beam	CY	30	10%	33	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 12,056	
27			6#5 Bars	LBS	1752	10%	1927	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 3,245	
28			#3 Bar Stirrups @ 36" O.C	LBS	237	10%	260	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 439	
29			(3'-0") 6 Mil. Vapor Barrier	SF	840	10%	924	0.002	\$ 46.90	\$ 0.09	\$ 0.23	\$ 0.32	\$ 299	
					SLAB									
30			5" THK Concrete Slab	CY	92	10%	102	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 36,832	
31	#3 Bar @ 16" O.C E.W	LBS	3384	10%	3722	0.015	\$ 46.90	\$ 0.70	\$ 0.98	\$ 1.68	\$ 6,267			
32	6 Mil. Vapor Barrier	SF	5985	10%	6583	0.002	\$ 46.90	\$ 0.09	\$ 0.23	\$ 0.32	\$ 2,132			
33	2" Cushion Sand	SF	5985	10%	6583	0.004	\$ 46.90	\$ 0.19	\$ 0.48	\$ 0.67	\$ 4,395			
34	18" THK Compacted Selected Fill	SF	5985	10%	6583	0.013	\$ 46.90	\$ 0.61	\$ 0.74	\$ 1.35	\$ 8,886			
35	6" Recompacted Existing Soil	SF	5985	10%	6583	0.005	\$ 46.90	\$ 0.23	\$ -	\$ 0.23	\$ 1,544			

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
 Project ID: 1005-26
 Scope: GC



Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
			THICKENED EDGE										
36			Thickened Edge Concrete - 3000 PSI	CY	3	10%	3	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 1,033
37			Thickened Edge Concrete - 3000 PSI	CY	3	10%	4	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 1,355
38			Thickened Edge Concrete - 3000 PSI	CY	0.5	10%	1	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 196
			HVAC UNIT FOOTING										
39			3'-0" x 3'-0" x 0'-4" Concrete Pad for Condensing Unit	CY	0.11	10%	0	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 44
			CONCRETE FINISHES										
			SEALED CONCRETE										
40			Sealed Concrete	SF	5128	10%	5641	0.033	\$ 46.90	\$ 1.55	\$ 0.92	\$ 2.47	\$ 13,920
SUBTOTAL \$													117,911
MASONRY													
			BRICK VENEER										
41	A2.0-A7.0	Plan Notes	Brick Veneer	SF	37	10%	41	0.200	\$ 46.90	\$ 9.38	\$ 11.32	\$ 20.70	\$ 842
SUBTOTAL \$													842
WOOD, PLASTIC & COMPOSITES													
			UN-FINISH CARPENTRY										
			HEADER										
42			2x10 Header	LF	93	10%	103	0.042	\$ 43.50	\$ 1.83	\$ 2.05	\$ 3.88	\$ 398
43			2x8 Header	LF	15	10%	16	0.040	\$ 43.50	\$ 1.74	\$ 1.82	\$ 3.56	\$ 57
			DECK FRAMING										
			JOIST FRAMING										
44			2x10 Floor Joists @ 16" O.C (1471 SF)	LF	1106	10%	1217	0.042	\$ 43.50	\$ 1.83	\$ 2.05	\$ 3.88	\$ 4,717
45			3/4" Plywood Sheathing	SF	1471	10%	1618						
46			No of Sheets (4x8)	EA	51	0%	51	0.640	\$ 43.50	\$ 27.84	\$ 41.92	\$ 69.76	\$ 3,527
47			Screws	EA	3792	0%	3792	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 406
			BLOCKING										
48			2x10 Blocking	LF	76	10%	83	0.042	\$ 43.50	\$ 1.83	\$ 2.05	\$ 3.88	\$ 323
			FINISH CARPENTRY										
			MILLWORK										
49			2' D x 2'-10" H Base Cabinets W/Doors and Hardware's	LF	16	10%	18	1.240	\$ 43.50	\$ 53.94	\$ 155.00	\$ 208.94	\$ 3,677
50			1' D x 2'-8" H Wall Mounted Cabinets W/MDF Shelves Inside	LF	16	10%	18	1.070	\$ 43.50	\$ 46.55	\$ 132.85	\$ 179.40	\$ 3,157
			Note: All Millwork Is To Receive Plastic Laminate Finish										
SUBTOTAL \$													16,263
THERMAL AND MOISTURE PROTECTION													
			EXTERIOR FINISHES										
			METAL SIDING										
51			1-1/2" Metal Siding -26 GA. -Color To Be Selected By Owner	SF	6908	10%	7599	0.045	\$ 43.00	\$ 1.94	\$ 4.54	\$ 6.48	\$ 49,202
52			Vinyl Backing R-13 Insulation	SF	6908	10%	7599	0.011	\$ 43.00	\$ 0.47	\$ 0.82	\$ 1.29	\$ 9,825
			EIPS FINISH										
53			EIPS Finish	SF	4516	10%	4968	0.055	\$ 43.00	\$ 2.37	\$ 1.59	\$ 3.96	\$ 19,647

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
Project ID: 1005-26
Scope: GC



Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
54			2" Thk Insulation Board	SF	4516	10%	4968	0.012	\$ 43.00	\$ 0.52	\$ 1.44	\$ 1.96	\$ 9,717
55			EIFS Trim	LF	888	10%	977	0.075	\$ 43.00	\$ 3.23	\$ 3.57	\$ 6.80	\$ 6,637
56			Rake Trim	LF	235	10%	259	0.033	\$ 43.00	\$ 1.42	\$ 2.05	\$ 3.47	\$ 897

SUBTOTAL \$ 95,925

OPENINGS

			DOORS											
57	A2.0-A7.0	Plan Notes	12' W x 12' H Aluminum Insulated Roll Up Overhead Door	EA	1	0%	1	39.890	\$ 54.50	\$ 2,174.01	\$ 7,977.60	\$ 10,151.61	\$ 10,152	
58			(2) 3' W x 7' H x 1-3/4" Thk Tempered Glass Aluminum Storefront Door	EA	2	0%	2	11.470	\$ 54.50	\$ 625.12	\$ 1,911.00	\$ 2,536.12	\$ 5,072	
59			3' W x 7' H x 1-3/4" Metal Door W/Hollow Metal Frame	EA	2	0%	2	7.040	\$ 54.50	\$ 383.68	\$ 1,171.80	\$ 1,555.48	\$ 3,111	
60			(2) 3' x 6'-8" x 1-5/8" Solid Core Wood Door W/Knock down Frame	EA	3	0%	3	7.810	\$ 54.50	\$ 425.65	\$ 1,300.65	\$ 1,726.30	\$ 5,179	
61			3' x 6'-8" x 1-5/8" Solid Core Single Wood Door W/Knock down Frame	EA	2	0%	2	5.210	\$ 54.50	\$ 283.95	\$ 650.33	\$ 934.27	\$ 1,869	
62			(2) 3' x 7'-0" x 1-3/4" Solid Core Wood Door W/Knock down Frame	EA	3	0%	3	8.190	\$ 54.50	\$ 446.36	\$ 1,365.00	\$ 1,811.36	\$ 5,434	
63			(2) 3' x 6'-8" x 1-5/8" Solid Core Wood Door W/Knock down Frame	EA	1	0%	1	7.810	\$ 54.50	\$ 425.65	\$ 1,300.65	\$ 1,726.30	\$ 1,726	
			HARDWARES											
64			(3) Hinges Butts	EA	10	0%	10	0.220	\$ 54.50	\$ 11.99	\$ 36.30	\$ 48.29	\$ 483	
65			(4) Hinges Butts	EA	4	0%	4	0.260	\$ 54.50	\$ 14.17	\$ 41.99	\$ 56.16	\$ 225	
66			Self Closing Device	EA	10	0%	10	1.280	\$ 54.50	\$ 69.76	\$ 212.00	\$ 281.76	\$ 2,818	
67			Panic Exit Device	EA	8	0%	8	1.890	\$ 54.50	\$ 103.01	\$ 376.90	\$ 479.91	\$ 3,839	
68			Lockset Handel	EA	4	0%	4	0.510	\$ 54.50	\$ 27.80	\$ 85.00	\$ 112.80	\$ 451	
69			Secure One Leaf	EA	9	0%	9	0.380	\$ 54.50	\$ 20.71	\$ 63.20	\$ 83.91	\$ 755	
70			Aluminum Threshold	EA	4	0%	4	0.260	\$ 54.50	\$ 14.17	\$ 41.99	\$ 56.16	\$ 225	
71			Exterior Pull Handle	EA	4	0%	4	0.510	\$ 54.50	\$ 27.80	\$ 85.00	\$ 112.80	\$ 451	
72			Wall Bumper Stop	EA	2	0%	2	0.030	\$ 54.50	\$ 1.64	\$ 3.40	\$ 5.04	\$ 10	
73			Push/Pull Plate	EA	2	0%	2	0.270	\$ 54.50	\$ 14.72	\$ 44.80	\$ 59.52	\$ 119	
			WINDOWS											
74			Tag A: 2' W x 6' H Double Insulated Aluminum Fixed Glass Window	EA	9	0%	9	4.200	\$ 54.50	\$ 228.90	\$ 426.00	\$ 654.90	\$ 5,894	
75			12' W x 2' H Double Insulated Aluminum Fixed Glass Window	EA	2	0%	2	8.400	\$ 54.50	\$ 457.80	\$ 852.00	\$ 1,309.80	\$ 2,620	

SUBTOTAL \$ 50,432

FINISHES

DRY WALL ASSEMBLIES													
76			Exterior Wall As:	SF	5244	LF	228	H	23				
			One Layer of 5/8" Gypsum Board on One Side	SF	5244								
77			No of Sheets (4x8)	EA	180	0%	180	0.384	\$ 43.50	\$ 16.70	\$ 16.48	\$ 33.18	\$ 5,982
78			Tapping	LF	2622	10%	2884	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 936
79			Joint Compound	LBS	682	10%	750	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 1,241
80			Screws	EA	8653	0%	8653	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 926
			7/16" OSB Sheathing @ Exterior	SF	5244								
81			No of Sheets (4x8)	EA	180	0%	180	0.640	\$ 43.50	\$ 27.84	\$ 29.44	\$ 57.28	\$ 10,325
82			Nails	EA	13520	0%	13520	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 1,447

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150

Project ID: 1005-26

Scope: GC



Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
83			6" Metal Studs @ 24' L -20 Gauge	EA	171	0%	171	0.912	\$ 43.50	\$ 39.67	\$ 40.56	\$ 80.23	\$ 13,754
84			6" Metal Runner At Top @ 10' L -20 Gauge	EA	23	0%	23	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 762
85			6" Metal Runner At Bottom @ 10' L -20 Gauge	EA	23	0%	23	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 762
86			R-19 Full Batt Fiberglass Insulation	SF	5244	10%	5768	0.011	\$ 43.50	\$ 0.48	\$ 0.92	\$ 1.40	\$ 8,067
87			8" Z Girt	LF	228	10%	251	0.040	\$ 43.50	\$ 1.74	\$ 5.96	\$ 7.70	\$ 1,931
88			Acoustical Sealant @ All Penetrations	LF	456	10%	502	0.014	\$ 43.50	\$ 0.61	\$ 0.10	\$ 0.71	\$ 356
89			Exterior Wall As:	SF	1744	LF	109	H	16				
			One Layer of 5/8" Gypsum Board on One Side	SF	1744								
			No of Sheets (4x8)	EA	60	0%	60	0.384	\$ 43.50	\$ 16.70	\$ 16.48	\$ 33.18	\$ 1,989
91			Tapping	LF	872	10%	959	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 311
92			Joint Compound	LBS	227	10%	249	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 413
93			Screws	EA	2878	0%	2878	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 308
			7/16" OSB Sheathing @ Exterior	SF	1744								
94			No of Sheets (4x8)	EA	60	0%	60	0.640	\$ 43.50	\$ 27.84	\$ 29.44	\$ 57.28	\$ 3,434
95			Nails	EA	4496	0%	4496	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 481
96			6" Metal Studs @ 16' L -20 Gauge	EA	82	0%	82	0.608	\$ 43.50	\$ 26.45	\$ 27.04	\$ 53.49	\$ 4,384
97			6" Metal Runner At Top @ 10' L -20 Gauge	EA	11	0%	11	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 364
98			6" Metal Runner At Bottom @ 10' L -20 Gauge	EA	11	0%	11	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 364
99			R-19 Full Batt Fiberglass Insulation	SF	1744	10%	1918	0.011	\$ 43.50	\$ 0.48	\$ 0.92	\$ 1.40	\$ 2,683
100			8" Z Girt	LF	109	10%	120	0.040	\$ 43.50	\$ 1.74	\$ 5.96	\$ 7.70	\$ 923
101			Acoustical Sealant @ All Penetrations	LF	218	10%	240	0.014	\$ 43.50	\$ 0.61	\$ 0.10	\$ 0.71	\$ 170
102			6" Metal Stud Interior Wall As:	SF	1725	LF	75	H	23				
			One Layer of 5/8" Gypsum Board on Both Side	SF	3450								
103			No of Sheets (4x8)	EA	119	0%	119	0.384	\$ 43.50	\$ 16.70	\$ 16.48	\$ 33.18	\$ 3,935
104			Tapping	LF	1725	10%	1898	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 616
105			Joint Compound	LBS	449	10%	493	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 816
106			Screws	EA	5693	0%	5693	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 609
107			6" Metal Studs @ 24' L -20 Gauge	EA	56	0%	56	0.912	\$ 43.50	\$ 39.67	\$ 40.56	\$ 80.23	\$ 4,524
108			6" Metal Runner At Top @ 10' L -20 Gauge	EA	8	0%	8	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 251
109			6" Metal Runner At Bottom @ 10' L -20 Gauge	EA	8	0%	8	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 251
110			R-19 Full Batt Fiberglass Insulation	SF	1725	10%	1898	0.011	\$ 43.50	\$ 0.48	\$ 0.92	\$ 1.40	\$ 2,654
111			Acoustical Sealant @ All Penetrations	LF	300	10%	330	0.014	\$ 43.50	\$ 0.61	\$ 0.10	\$ 0.71	\$ 234
112			6" Metal Stud Interior Wall As:	SF	2507	LF	109	H	23				
			One Layer of 5/8" Gypsum Board on Both Side	SF	4422								
113			No of Sheets (4x8)	EA	152	0%	152	0.384	\$ 43.50	\$ 16.70	\$ 16.48	\$ 33.18	\$ 5,044
114			Tapping	LF	2211	10%	2432	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 789
115			Joint Compound	LBS	575	10%	632	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 1,047
116			Screws	EA	7296	0%	7296	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 781

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
 Project ID: 1005-26
 Scope: GC



Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
117	A2.0-A7.0	Plan Notes	6" Metal Studs @ 24' L -20 Gauge	EA	82	0%	82	0.912	\$ 43.50	\$ 39.67	\$ 40.56	\$ 80.23	\$ 6,575
118			6" Metal Runner At Top @ 10' L -20 Gauge	EA	11	0%	11	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 364
119			6" Metal Runner At Bottom @ 10' L -20 Gauge	EA	11	0%	11	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 364
120			Acoustical Sealant @ All Penetrations	LF	436	10%	480	0.014	\$ 43.50	\$ 0.61	\$ 0.10	\$ 0.71	\$ 340
121			Pony Wall As:	SF	296	LF	74	H	4				
			One Layer of 5/8" Gypsum Board on Both Side	SF	592								
122			No of Sheets (4x8)	EA	20	0%	20	0.384	\$ 43.50	\$ 16.70	\$ 16.48	\$ 33.18	\$ 675
123			Tapping	LF	296	10%	326	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 106
124			Joint Compound	LBS	77	10%	85	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 140
125			Screws	EA	977	0%	977	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 105
126			6" Metal Studs @ 8' L -20 Gauge	EA	56	0%	56	0.304	\$ 43.50	\$ 13.22	\$ 13.52	\$ 26.74	\$ 1,488
127			6" Metal Runner At Top @ 10' L -20 Gauge	EA	7	0%	7	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 247
128			6" Metal Runner At Bottom @ 10' L -20 Gauge	EA	7	0%	7	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 247
129			Acoustical Sealant @ All Penetrations	LF	296	10%	326	0.014	\$ 43.50	\$ 0.61	\$ 0.10	\$ 0.71	\$ 231
130			2x6 Cap	LF	74	10%	81	0.038	\$ 43.50	\$ 1.65	\$ 1.55	\$ 3.20	\$ 261
131			Plumbing Wall As:	SF	124	LF	13	H	9.5				
			One Layer of 5/8" Moisture Resistant Gypsum Board on Both Side	SF	247								
132			No of Sheets (4x8)	EA	8	0%	8	0.384	\$ 43.50	\$ 16.70	\$ 17.12	\$ 33.82	\$ 287
133			Tapping	LF	124	10%	136	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 44
134			Joint Compound	LBS	32	10%	35	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 58
135			Screws	EA	408	0%	408	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 44
136			6" Double Metal Studs @ 10' L -20 Gauge	EA	20	0%	20	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 654
137			6" Metal Runner At Top @ 10' L -20 Gauge	EA	1	0%	1	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 43
138			6" Metal Runner At Bottom @ 10' L -20 Gauge	EA	1	0%	1	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 43
139			Acoustical Sealant @ All Penetrations	LF	52	10%	57	0.014	\$ 43.50	\$ 0.61	\$ 0.10	\$ 0.71	\$ 41
140			6" Metal Stud Interior Wall As:	SF	228	LF	24	H	9.5				
			One Layer of 5/8" Gypsum Board on One Side	SF	228								
141			No of Sheets (4x8)	EA	8	0%	8	0.384	\$ 43.50	\$ 16.70	\$ 16.48	\$ 33.18	\$ 260
142			Tapping	LF	114	10%	125	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 41
143			Joint Compound	LBS	30	10%	33	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 54
144			Screws	EA	376	0%	376	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 40
			One Layer of 5/8" Moisture Resistant Gypsum Board on One Side	SF	228								
145			No of Sheets (4x8)	EA	8	0%	8	0.384	\$ 43.50	\$ 16.70	\$ 17.12	\$ 33.82	\$ 265
146			Tapping	LF	114	10%	125	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 41
147			Joint Compound	LBS	30	10%	33	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 54
148			Screws	EA	376	0%	376	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 40
149			6" Metal Studs @ 10' L -20 Gauge	EA	18	0%	18	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 603

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
Project ID: 1005-26
Scope: GC



Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
150			6" Metal Runner At Top @ 10' L -20 Gauge	EA	2	0%	2	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 80
151			6" Metal Runner At Bottom @ 10' L -20 Gauge	EA	2	0%	2	0.380	\$ 43.50	\$ 16.53	\$ 16.90	\$ 33.43	\$ 80
152			Acoustical Sealant @ All Penetrations	LF	96	10%	106	0.014	\$ 43.50	\$ 0.61	\$ 0.10	\$ 0.71	\$ 75
			CEILING FINISHES										
			GYPSUM BOARD:										
			5/8" Gypsum Board Ceiling	SF	404								
153			No of Sheets (4x8)	EA	14	0%	14	0.480	\$ 43.50	\$ 20.88	\$ 21.76	\$ 42.64	\$ 592
154			Tapping	LF	202	10%	222	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 72
155			Joint Compound	LBS	53	10%	58	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 96
156			Screws	EA	667	0%	667	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 71
			5/8" Moisture Resistant Gypsum Board Ceiling	SF	329								
157			No of Sheets (4x8)	EA	11	0%	11	0.480	\$ 43.50	\$ 20.88	\$ 24.00	\$ 44.88	\$ 508
158			Tapping	LF	165	10%	181	0.007	\$ 43.50	\$ 0.30	\$ 0.02	\$ 0.32	\$ 59
159			Joint Compound	LBS	43	10%	47	0.030	\$ 43.50	\$ 1.31	\$ 0.35	\$ 1.66	\$ 78
160			Screws	EA	543	0%	543	0.002	\$ 43.50	\$ 0.09	\$ 0.02	\$ 0.11	\$ 58
			ACT CEILING										
161			2' x 4' x 5/8" Thk Suspended ACT Ceiling -Armstrong #755 (Surface Mounted Tees)	SF	264	10%	290	0.036	\$ 43.50	\$ 1.57	\$ 2.77	\$ 4.34	\$ 1,259
			FLOOR FINISHES										
162			12" x 12" Vinyl Composite Tile Flooring Mfr/Model: Armstrong Fed Spec SS-T-312B Standard Excelon	SF	475	10%	523	0.040	\$ 46.50	\$ 1.86	\$ 2.96	\$ 4.82	\$ 2,518
163			12" x 12" Quarry Tile W/Grout	SF	326	10%	359	0.075	\$ 46.50	\$ 3.49	\$ 6.09	\$ 9.58	\$ 3,434
			BASE FINISHES										
164			4" H Vinyl Base Mfr/Model: Armstrong #165 Almond	LF	541	10%	595	0.030	\$ 46.50	\$ 1.40	\$ 1.85	\$ 3.25	\$ 1,931
165			6" H Ceramic Tile Base	LF	118	10%	130	0.038	\$ 46.50	\$ 1.77	\$ 2.84	\$ 4.61	\$ 598
			WALL FINISHES										
			WALL TILES										
166			10" x 10" Ceramic Wall Tiles	SF	696	10%	766	0.075	\$ 46.50	\$ 3.49	\$ 4.88	\$ 8.37	\$ 6,406
			PAINTING										
			WALL PAINT										
167			Wall Paint -1 Coat Primer And 2 Coat Finish	SF	15460	10%	17006	0.020	\$ 41.41	\$ 0.83	\$ 0.40	\$ 1.23	\$ 20,887
			CEILING PAINT										
168			Exposed Structure Paint	SF	4940	10%	5434	0.022	\$ 41.41	\$ 0.91	\$ 0.45	\$ 1.36	\$ 7,396
169			Ceiling Paint -1 Coat Primer And 2 Coat Finish	SF	733	10%	806	0.020	\$ 41.41	\$ 0.83	\$ 0.40	\$ 1.23	\$ 990
SUBTOTAL \$													144,810
SPECIALITIES													
			BATHROOM ACCESSORIES										
170			Wall Mirror -1/4" Polished Plated Glass Copper Protected Mirror	EA	2	0%	2	1.850	\$ 54.50	\$ 100.83	\$ 234.00	\$ 334.83	\$ 670
171			Stainless Steel Grab Bar	EA	4	0%	4	0.650	\$ 54.50	\$ 35.43	\$ 42.19	\$ 77.62	\$ 310

DETAILED BREAKDOWN OF ITEMS


Project Name:	LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
---------------	--

Project ID: 1005-26

Project ID: 1000-10
Scope: GC



Scope: GC

 ACE SERVICES

Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
172	A2.0-A7.0	Plan Notes	Wall Mounted Soap Dispenser -Bob rick #B155	EA	4	0%	4	0.480	\$ 54.50	\$ 26.16	\$ 26.91	\$ 53.07	\$ 212	
173			Chrome Plated Tissue Paper Holder	EA	3	0%	3	0.600	\$ 54.50	\$ 32.70	\$ 55.10	\$ 87.80	\$ 263	
174			Sanitary Napkin Disposal	EA	2	0%	2	0.750	\$ 54.50	\$ 40.88	\$ 102.80	\$ 143.68	\$ 287	
175			Fold Down Changing Table	EA	2	0%	2	1.750	\$ 54.50	\$ 95.38	\$ 274.92	\$ 370.30	\$ 741	
176			Chrome Plated Towel Holder	EA	2	0%	2	0.420	\$ 54.50	\$ 22.89	\$ 31.82	\$ 54.71	\$ 109	
177			Restroom Sign	EA	2	0%	2	0.720	\$ 54.50	\$ 39.24	\$ 56.30	\$ 95.54	\$ 191	
			TOILET COMPARTMENTS											
178			8' H Overhead Metal Partition Wall Height Assumed	LF	30	10%	33	1.100	\$ 54.50	\$ 59.95	\$ 201.36	\$ 261.31	\$ 8,623	
			FIRE EXTINGUISHER											
179			Portable Fire Extinguisher Recessed In Wall Cabinet	EA	7	0%	7	0.900	\$ 54.50	\$ 49.05	\$ 89.00	\$ 138.05	\$ 966	

	SUBTOTAL \$	12,374
--	-------------	--------

EQUIPMENTS

[illegible]

	SUBTOTAL \$	294
--	-------------	-----

[illegible]

			COUNTERTOP										
181	A2.0-A7.0	Plan Notes	Solid Surface Countertop -Assumed	SF	59	10%	65	0.350	\$ 54.50	\$ 19.08	\$ 63.19	\$ 82.27	\$ 5,339
182			Vanity Countertop	SF	19	10%	21	0.350	\$ 54.50	\$ 19.08	\$ 63.19	\$ 82.27	\$ 1,719
			BACKSPLASH										
183			4" H Backsplash	LF	16	10%	18	0.100	\$ 54.50	\$ 5.45	\$ 10.44	\$ 15.89	\$ 280

	SUBTOTAL	\$	7.338
--	----------	----	-------

SPECIAL CONSTRUCTION

			METAL BUILDING SYSTEM										
			PRE ENGINEERED METAL BUILDING										
184	S2.0	Plan Notes	Pre Engineered Metal Building (Ridge Height : 30'-4" H & Eave Height : 16'-0" H) -Steel Framing -Cold Formed Metal Purlins @ 5'-0" O.C E.W (Min 50 Ksi Yield Strength, ASTM-607, Grade 50) -Standing Seam Metal Roof W/All Accessories And Flashings -One Shop Coat of Primer -Must Meet Federal Spec. TTP-636 Note: By Pre Engineered Metal Building Mfr.	SF	6465	10%	7112	0.350	\$ 54.50	\$ 19.08	\$ 28.44	\$ 47.52	\$ 337,903
185			Pre Engineered Metal Canopy Note: By Pre Engineered Metal Building Mfr.	SF	155	10%	171	0.300	\$ 54.50	\$ 16.35	\$ 48.27	\$ 64.62	\$ 11,018

	SUBTOTAL \$	348,921
--	-------------	---------

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
 Project ID: 1005-26
 Scope: GC



Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
FIRE SUPPRESSION													
			FIRE SUPPRESSION SPRINKLER SYSTEM										
186	A2.0-A7.0	General Notes	Allowance For Fire Sprinkler System (6383 SF) -Includes Installation Of Sprinkler Heads, Pipes, Fittings, Hangers And Accessories.	LS	1	0%	1	70.213	\$ 75.30	\$ 5,287.04	\$ 3,510.65	\$ 8,797.69	\$ 8,798
													SUBTOTAL \$ 8,798

PLUMBING												
			PIPING									
			WATER PIPES									
187			1/2" Cold Water Pipe	LF	17	10%	19	0.104	\$ 75.30	\$ 7.83	\$ 3.46	\$ 11.29 \$ 217
188			3/4" Cold Water Pipe	LF	34	10%	38	0.110	\$ 75.30	\$ 8.28	\$ 6.02	\$ 14.30 \$ 541
189			1" Cold Water Pipe	LF	115	10%	126	0.124	\$ 75.30	\$ 9.34	\$ 7.33	\$ 16.67 \$ 2,102
190			3/4" Hot Water Pipe	LF	18	10%	20	0.110	\$ 75.30	\$ 8.28	\$ 6.02	\$ 14.30 \$ 282
191			Type K, 1" Dia Copper Water Line	LF	41	10%	45	0.124	\$ 75.30	\$ 9.34	\$ 8.12	\$ 17.46 \$ 787
			WASTE PIPES									
192			2" Sanitary Sewer Piping	LF	57	10%	63	0.190	\$ 75.30	\$ 14.31	\$ 4.95	\$ 19.26 \$ 1,207
193			3" Sanitary Sewer Piping	LF	120	10%	132	0.211	\$ 75.30	\$ 15.89	\$ 7.43	\$ 23.31 \$ 3,071
194			4" Sanitary Sewer Piping	LF	25	10%	28	0.233	\$ 75.30	\$ 17.54	\$ 9.90	\$ 27.44 \$ 765
			VENT PIPES									
195			1 1/4" Vent Pipe	LF	49	10%	53	0.150	\$ 75.30	\$ 11.30	\$ 3.09	\$ 14.39 \$ 768
196			1 1/2" Vent Pipe	LF	26	10%	28	0.175	\$ 75.30	\$ 13.18	\$ 3.71	\$ 16.89 \$ 477
197			2" Vent Pipe	LF	4	10%	4	0.190	\$ 75.30	\$ 14.31	\$ 4.95	\$ 19.26 \$ 82
			PLUMBING FIXTURES									
198			Floor Drain w/ Trap Primer & Deep Seal P-Trap Model: JOSAM 30003-5A-50	EA	3	0%	3	2.120	\$ 75.30	\$ 159.64	\$ 227.99	\$ 387.63 \$ 1,163
199			Lavatory, Counter-Mounted Delf Rimming Dual Hand Control Model: K-2053, 8" CC w/ Delta Model 3549 WFL.CHDF	EA	4	0%	4	4.750	\$ 75.30	\$ 357.68	\$ 354.90	\$ 712.58 \$ 2,850
200			Tank-Type Water Closet Model: K-3575-RA W/ k-4731 Seat & Manual Lever	EA	3	0%	3	4.330	\$ 75.30	\$ 326.05	\$ 377.58	\$ 703.63 \$ 2,111
201			Wall Mounted Urinal Model: K-5016-ET	EA	1	0%	1	4.200	\$ 75.30	\$ 316.26	\$ 216.98	\$ 533.24 \$ 533
202			Hub Drain w/ 1/2" Trap Primer& 2" Oval Funnel Model: JOSAM 30003-5A-50	EA	3	0%	3	2.120	\$ 75.30	\$ 159.64	\$ 227.99	\$ 387.63 \$ 1,163
203			18 GA Kitchen Sink Double Compartment w/ Faucet Model: ELKAY L2D3322-4	EA	1	0%	1	5.200	\$ 75.30	\$ 391.56	\$ 1,626.00	\$ 2,017.56 \$ 2,018
204			Electrical Water Cooler w/ Water Sentry VII Filter System 120V/1P Model: LMABFTL8C	EA	2	0%	2	12.250	\$ 75.30	\$ 922.43	\$ 1,928.25	\$ 2,850.68 \$ 5,701
205			Temperature Limiting Devices Model: ASSE 1070	EA	5	0%	5	1.650	\$ 75.30	\$ 124.25	\$ 166.09	\$ 290.34 \$ 1,452
			VALVE									
206			1" Dia Shut-Off Valve (Gate Type) w/ Valve Box in Concrete & Iron Lid	EA	1	0%	1	0.414	\$ 75.30	\$ 31.16	\$ 22.99	\$ 54.15 \$ 54
207			ASME T & P Relief Valve	EA	1	0%	1	1.250	\$ 75.30	\$ 94.13	\$ 76.13	\$ 170.26 \$ 170

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
 Project ID: 1005-26
 Scope: GC



Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
208			Shut Off Valve	EA	1	0%	1	0.414	\$ 75.30	\$ 31.16	\$ 22.99	\$ 54.15	\$ 54
209			Cut Off Valve	EA	2	0%	2	0.540	\$ 75.30	\$ 40.65	\$ 29.99	\$ 70.64	\$ 141
210			Gate Valve	EA	3	0%	3	1.350	\$ 75.30	\$ 101.66	\$ 119.00	\$ 220.66	\$ 662
			ELECTRIC WATER HEATER										
211			Water Heater - 1 30 Gallons Storage 208 V/1 Ph Model: DEL-30 Manufacturer: A O Smith	EA	1	0%	1	8.250	\$ 75.30	\$ 621.23	\$ 2,148.56	\$ 2,769.79	\$ 2,770
			DEVICES										
212			Reduced Pressure Backflow Preventer Assembly Model: FEBCI 860	EA	1	0%	1	2.760	\$ 75.30	\$ 207.83	\$ 344.97	\$ 552.80	\$ 553
213			ST-5 Expansion Tank Model: AMTROL	EA	1	0%	1	1.100	\$ 75.30	\$ 82.83	\$ 120.00	\$ 202.83	\$ 203
			MISC.										
214			2" Deep Auxiliary Drain Pan	EA	1	0%	1	1.050	\$ 75.30	\$ 79.07	\$ 68.94	\$ 148.01	\$ 148
215			Heat Trap	EA	2	0%	2	0.650	\$ 75.30	\$ 48.95	\$ 23.86	\$ 72.81	\$ 146
216			RPZ Backflow Preventer	EA	1	0%	1	4.600	\$ 75.30	\$ 346.38	\$ 1,275.99	\$ 1,622.37	\$ 1,622
217			Hose Hydrant, Freeze-Proof w/ Control Key & Integral Vacuum Breaker & Union Below Model: JOSAM 71050	EA	2	0%	2	2.160	\$ 75.30	\$ 162.65	\$ 336.33	\$ 498.98	\$ 998
218			Double Grade Cleanout 2'-0" x 1'-0" x 0'-6" Concrete	EA	2	0%	2	4.250	\$ 75.30	\$ 320.03	\$ 569.99	\$ 890.02	\$ 1,780
219			Grade Cleanout	EA	1	0%	1	2.360	\$ 75.30	\$ 177.71	\$ 314.50	\$ 492.21	\$ 492
SUBTOTAL \$													37,084

HVAC

			DUCTS AND PIPING										
			CIRCULAR DUCTS										
220			8" Dia Flexible Duct	LF	10	10%	11	0.121	\$ 76.25	\$ 9.19	\$ 4.85	\$ 14.05	\$ 150
221			10" Dia Flexible Duct	LF	8	10%	9	0.151	\$ 76.25	\$ 11.49	\$ 6.07	\$ 17.56	\$ 154
222			12" Dia Circular Duct	LF	93	10%	102	0.452	\$ 76.25	\$ 34.48	\$ 18.20	\$ 52.68	\$ 5,378
223			14" Dia Circular Duct	LF	44	10%	49	0.528	\$ 76.25	\$ 40.22	\$ 21.23	\$ 61.46	\$ 3,006
224			15" Dia Circular Duct	LF	50	10%	55	0.565	\$ 76.25	\$ 43.10	\$ 22.75	\$ 65.85	\$ 3,628
225			16" Dia Circular Duct	LF	62	10%	69	0.603	\$ 76.25	\$ 45.97	\$ 24.27	\$ 70.24	\$ 4,816
226			18" Dia Circular Duct	LF	90	10%	99	0.678	\$ 76.25	\$ 51.72	\$ 27.30	\$ 79.02	\$ 7,810
227			10" Dia Circular Duct	LF	31	10%	34	0.377	\$ 76.25	\$ 28.73	\$ 15.17	\$ 43.90	\$ 1,481
			RECTANGULAR DUCTS										
228			8" x 6" Rectangular Duct	LF	5	10%	6	0.336	\$ 76.25	\$ 25.62	\$ 8.93	\$ 34.55	\$ 192
			TRANSITION										
229			12" Dia to 14" Dia Duct Transition	EA	3	0%	3	0.332	\$ 76.25	\$ 25.35	\$ 22.16	\$ 47.51	\$ 143
230			12" Dia to 15" Dia Duct Transition	EA	3	0%	3	0.345	\$ 76.25	\$ 26.32	\$ 23.01	\$ 49.33	\$ 148
231			14" Dia to 18" Dia Duct Transition	EA	1	0%	1	0.409	\$ 76.25	\$ 31.19	\$ 27.27	\$ 58.47	\$ 58
232			14" Dia to 16" Dia Duct Transition	EA	2	0%	2	0.384	\$ 76.25	\$ 29.24	\$ 25.57	\$ 54.81	\$ 110
233			15" Dia to 18" Dia Duct Transition	EA	3	0%	3	0.422	\$ 76.25	\$ 32.17	\$ 28.13	\$ 60.30	\$ 181
234			16" Dia to 18" Dia Duct Transition	EA	2	0%	2	0.435	\$ 76.25	\$ 33.14	\$ 28.98	\$ 62.12	\$ 124

DETAILED BREAKDOWN OF ITEMS


Project Name:	LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
---------------	--

Project ID: 1005-26

Project ID: 100010
Scope: GC



Scope: GC

 ACE SERVICES

Date: 1-Mar-25

[illegible]

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
 Project ID: 1005-26
 Scope: GC



ACE SERVICES

Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
250	M2.1, M3.1, M4.1	Plan Notes	Model: SP-A290 Manufacturer: Greenheck EF-3 Exhaust Fan, Suspended Ceiling Mounted , In-Line 275 CFM 120V, 1 Ph, 81W	EA	1	0%	1	2.460	\$ 76.25	\$ 187.58	\$ 306.75	\$ 494.33	\$ 494
251			Model: SP-A290 Manufacturer: Greenheck EF-4 Exhaust Fan, Suspended Ceiling Mounted , In-Line 250 CFM 120V, 1 Ph, 81W	EA	1	0%	1	2.460	\$ 76.25	\$ 187.58	\$ 306.75	\$ 494.33	\$ 494
			AIR HANDLING UNITS										
252			AHU-7 1625 Total AHU CFM 325 CFM Out Air 208 V/1 Phase Model: TAM4AOC48S41SD Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	8.610	\$ 76.25	\$ 656.51	\$ 3,444.00	\$ 4,100.51	\$ 4,101
253			AHU-8 1500 Total AHU CFM 300 CFM Out Air 208 V/1 Phase Model: TAM4AOC48S41SD Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	8.610	\$ 76.25	\$ 656.51	\$ 3,444.00	\$ 4,100.51	\$ 4,101
254			AHU-9 1200 Total AHU CFM 250 CFM Out Air 208 V/1 Phase Model: TAM4AOC48S41SD Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	8.610	\$ 76.25	\$ 656.51	\$ 3,444.00	\$ 4,100.51	\$ 4,101
255			AHU-10 1200 Total AHU CFM 250 CFM Out Air 208 V/1 Phase Model: TAM4AOC48S41SD Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	8.610	\$ 76.25	\$ 656.51	\$ 3,444.00	\$ 4,100.51	\$ 4,101
256			AHU-11 1500 Total AHU CFM 300 CFM Out Air 208 V/1 Phase Model: TAM4AOC48S41SD Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	8.610	\$ 76.25	\$ 656.51	\$ 3,444.00	\$ 4,100.51	\$ 4,101

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
Project ID: 1005-26
Scope: GC



ACE SERVICES

Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
257			AHU-12 Total AHU CFM 325 CFM Out Air 208 V/1 Phase Model: TAM4AOC48S41SD Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	8.610	\$ 76.25	\$ 656.51	\$ 3,444.00	\$ 4,100.51	\$ 4,101
			AIR CONDENSING UNIT										
258			CU-7 Ambient Temp.: 102 Unit MCA/MOCP: 18/30 Unit Voltage/Phase: 208/3 Model No. 4TTA3048D3 Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	7.590	\$ 76.25	\$ 578.74	\$ 3,033.96	\$ 3,612.70	\$ 3,613
259			CU-8 Ambient Temp.: 102 Unit MCA/MOCP: 18/30 Unit Voltage/Phase: 208/3 Model No. 4TTA3048D3 Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	7.590	\$ 76.25	\$ 578.74	\$ 3,033.96	\$ 3,612.70	\$ 3,613
260			CU-9 Ambient Temp.: 102 Unit MCA/MOCP: 18/30 Unit Voltage/Phase: 208/3 Model No. 4TTA3048D3 Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	7.590	\$ 76.25	\$ 578.74	\$ 3,033.96	\$ 3,612.70	\$ 3,613
261			CU-10 Ambient Temp.: 102 Unit MCA/MOCP: 18/30 Unit Voltage/Phase: 208/3 Model No. 4TTA3048D3 Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	7.590	\$ 76.25	\$ 578.74	\$ 3,033.96	\$ 3,612.70	\$ 3,613
262			CU-11 Ambient Temp.: 102 Unit MCA/MOCP: 18/30 Unit Voltage/Phase: 208/3 Model No. 4TTA3048D3 Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	7.590	\$ 76.25	\$ 578.74	\$ 3,033.96	\$ 3,612.70	\$ 3,613
263			CU-12 Ambient Temp.: 102 Unit MCA/MOCP: 18/30 Unit Voltage/Phase: 208/3 Model No. 4TTA3048D3 Note: Model no. is Reference only, contractor to provide the Exact equipment	EA	1	0%	1	7.590	\$ 76.25	\$ 578.74	\$ 3,033.96	\$ 3,612.70	\$ 3,613

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
 Project ID: 1005-26
 Scope: GC



ACE SERVICES

Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
MISC													
264			Unit Mounted Disconnect Switch	EA	2	0%	2	1.210	\$ 76.25	\$ 92.26	\$ 65.12	\$ 157.38	\$ 315
265			Switch w/ Time Delay Relay	EA	2	0%	2	1.030	\$ 76.25	\$ 78.54	\$ 41.20	\$ 119.74	\$ 239
266			Programmable Thermostat w/ Key Lock Cover	EA	2	0%	2	1.450	\$ 76.25	\$ 110.56	\$ 214.00	\$ 324.56	\$ 649
267			Termination Kit	EA	2	0%	2	1.360	\$ 76.25	\$ 103.70	\$ 88.91	\$ 192.61	\$ 385
268			Programmable Thermostat	EA	6	0%	6	1.450	\$ 76.25	\$ 110.56	\$ 214.00	\$ 324.56	\$ 1,947
269			Crankcase Heater	EA	6	0%	6	0.630	\$ 76.25	\$ 48.04	\$ 38.69	\$ 86.73	\$ 520
270			Filter Dryer	EA	6	0%	6	0.450	\$ 76.25	\$ 34.31	\$ 32.00	\$ 66.31	\$ 398
271			Moisture Indicating Sight Glass	EA	6	0%	6	0.820	\$ 76.25	\$ 62.53	\$ 41.06	\$ 103.59	\$ 622
272			Service Valve	EA	6	0%	6	0.540	\$ 76.25	\$ 41.18	\$ 36.33	\$ 77.51	\$ 465
273			Floor Return Air Plenum	EA	2	0%	2	1.650	\$ 76.25	\$ 125.81	\$ 220.77	\$ 346.58	\$ 693
274			20" x 20" Barometric Relief Hood Model: Green heck Model FGR- 20" x 20"	EA	1	0%	1	3.250	\$ 76.25	\$ 247.81	\$ 650.00	\$ 897.81	\$ 898
275			8" x 6" Termination Cap Model: WC-8	EA	2	0%	2	0.915	\$ 76.25	\$ 69.78	\$ 83.20	\$ 152.98	\$ 306
276			16" Dia Outside Air Duct Up Through	EA	2	0%	2	1.820	\$ 76.25	\$ 138.78	\$ 169.99	\$ 308.77	\$ 618
277			Roof Cap for Roof-Through Duct Model: GRSF-16	EA	2	0%	2	2.260	\$ 76.25	\$ 172.33	\$ 388.00	\$ 560.33	\$ 1,121
												SUBTOTAL \$	98,364
ELECTRICAL													
278			Allowance for Electrical Wiring And Conduiting (6383 SF)	LS	1	0%	1	223.000	\$ 78.20	\$ 17,438.60	\$ 5,724.00	\$ 23,162.60	\$ 23,163
LIGHTING													
279			2x4 LED Troffer Color: 4000K Lumens: 6253 Watts: 49 Model 2GTL4 60L LP840 Manufacturer: Lithonia	EA	6	0%	6	2.250	\$ 78.20	\$ 175.95	\$ 249.21	\$ 425.16	\$ 2,551
280			2x2 LED Troffer Color: 4000K Lumens: 3535 Watts: 29 Model 2GTL2 33L LP840 Manufacturer: Lithonia	EA	4	0%	4	1.190	\$ 78.20	\$ 93.06	\$ 108.07	\$ 201.13	\$ 805
281			High Bay Pendant Light Color: 4000K Lumens: 4975 Watts: 125 Model JCBL 18000LM DALR 40K 90CRI Manufacturer: Lithonia	EA	15	0%	15	3.340	\$ 78.20	\$ 261.19	\$ 477.10	\$ 738.29	\$ 11,074
282			Exterior Wall-Mounted Facade Color: 4000K Lumens: 7118 Watts: 87 Model: OLWX2 LED 90W 40K DDB M2 Manufacturer: Lithonia	EA	6	0%	6	2.920	\$ 78.20	\$ 228.34	\$ 416.00	\$ 644.34	\$ 3,866

DETAILED BREAKDOWN OF ITEMS									
-----------------------------	--	--	--	--	--	--	--	--	--


Project Name:	LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
---------------	--

Project ID: 1005-26

Project ID: 100010
Scope: GC



Scope: GC

 ACE SERVICES

Date: 1-Mar-25

[illegible]

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
 Project ID: 1005-26
 Scope: GC



Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
296			2 Pole, 25 AMP Breaker	EA	6	0%	6	0.600	\$ 78.20	\$ 46.92	\$ 40.00	\$ 86.92	\$ 522
297			2 Pole, 50 AMP Breaker	EA	1	0%	1	1.200	\$ 78.20	\$ 93.84	\$ 80.00	\$ 173.84	\$ 174
298			3 Pole, 30 AMP Breaker	EA	4	0%	4	0.803	\$ 78.20	\$ 62.83	\$ 53.56	\$ 116.39	\$ 466
299			3 Pole, 20 AMP Breaker	EA	2	0%	2	0.536	\$ 78.20	\$ 41.88	\$ 35.71	\$ 77.59	\$ 155
			CIRCUIT BREAKER - Panel P										
300			1 Pole, 20 AMP Breaker	EA	21	0%	21	0.385	\$ 78.20	\$ 30.11	\$ 25.67	\$ 55.78	\$ 1,171
301			2 Pole, 40 AMP Breaker	EA	1	0%	1	0.960	\$ 78.20	\$ 75.07	\$ 64.00	\$ 139.07	\$ 139
			POWER										
302			Duplex Receptacle	EA	15	0%	15	0.610	\$ 78.20	\$ 47.69	\$ 20.33	\$ 68.02	\$ 1,020
303			Ground Fault Interrupter Receptacle	EA	5	0%	5	1.249	\$ 78.20	\$ 97.66	\$ 41.63	\$ 139.29	\$ 696
304			Weather Proofed Ground Fault Interrupter Receptacle	EA	2	0%	2	1.395	\$ 78.20	\$ 109.09	\$ 46.50	\$ 155.59	\$ 311
			MICS.										
305			Integrated Photocell/Remote Photocell	EA	8	0%	8	1.030	\$ 78.20	\$ 80.55	\$ 41.40	\$ 121.95	\$ 976
306			Photo Electric Cell	EA	1	0%	1	1.100	\$ 78.20	\$ 86.02	\$ 48.20	\$ 134.22	\$ 134
307			Time Clock	EA	1	0%	1	1.550	\$ 78.20	\$ 121.21	\$ 374.10	\$ 495.31	\$ 495
308			6-Pole, 3A, 120V Coil	EA	1	0%	1	1.250	\$ 78.20	\$ 97.75	\$ 82.99	\$ 180.74	\$ 181
309			Wire Way	EA	1	0%	1	1.840	\$ 78.20	\$ 143.89	\$ 139.01	\$ 282.90	\$ 283
310			#1/0 Bare CU Grounding Conductors	EA	1	0%	1	1.260	\$ 78.20	\$ 98.53	\$ 58.60	\$ 157.13	\$ 157
SUBTOTAL \$													63,669

ELECTRONIC SAFETY AND SECURITY

	COVER PAGE	General Notes	FIRE ALARM SYSTEM										
311			Allowance For Fire Alarm System(6383 SF)	LS	1	0%	1	70.213	\$ 78.20	\$ 5,490.66	\$ 4,148.95	\$ 9,639.61	\$ 9,640
SUBTOTAL \$													9,640

EXTERIOR IMPROVEMENTS

			WOOD FENCE										
312			4' H Wood Screen Fence Around Condenser Units -Height Assumed	LF	26	10%	29	0.150	\$ 46.90	\$ 7.04	\$ 13.18	\$ 20.22	\$ 578
			SIGNAGES AND WHEEL STOP										
313			12" W x 6' L Precast Concrete Wheel Stop -(2)#3 Cont. Bars	EA	8	0%	8	0.900	\$ 46.90	\$ 42.21	\$ 80.00	\$ 122.21	\$ 978
314			12" W x 18" H Handicapped Parking Sign	EA	8	0%	8	1.280	\$ 46.90	\$ 60.03	\$ 128.93	\$ 188.96	\$ 1,512
315			18" Dia x 42" H Concrete Footing For Sign Posts	CY	2	10%	2	2.500	\$ 46.90	\$ 117.25	\$ 245.00	\$ 362.25	\$ 730
316			Excavation	CY	10	10%	11	0.550	\$ 46.90	\$ 25.80	\$ -	\$ 25.80	\$ 283
317			Formwork	SF	132	10%	145	0.035	\$ 46.90	\$ 1.64	\$ -	\$ 1.64	\$ 238
318			Backfill	CY	8	10%	9	0.450	\$ 46.90	\$ 21.11	\$ -	\$ 21.11	\$ 189
			LANDSCAPING										
			TREES										
319	L1.0-A1.0	Plan Notes	Botanic Name: lagerstromia Indica Common Name: Crape Myrtle -2" Cal x 6' H	EA	11	0%	11	2.088	\$ 46.90	\$ 97.93	\$ 375.00	\$ 472.93	\$ 5,202
			SHRUBS										
320			Common Name: Indian Hawthorn Size: 5 GAL x 3' H	EA	64	0%	64	0.425	\$ 46.90	\$ 19.93	\$ 49.66	\$ 69.59	\$ 4,454

DETAILED BREAKDOWN OF ITEMS

Project Name: LIGHT CHURCH 2606 JOHN WEST ROAD MESQUITE, TEXAS 75150
 Project ID: 1005-26
 Scope: GC



ACE SERVICES

Date: 1-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
321			Common Name: Dwarf Burford Holly Size: 5 GAL x 3' H	EA	26	0%	26	0.425	\$ 46.90	\$ 19.93	\$ 34.95	\$ 54.88	\$ 1,427
			GROUND COVER										
322			Common Name: Asian Jasmine 12" Spacing	SF	3083	10%	3391	0.015	\$ 46.90	\$ 0.70	\$ 1.87	\$ 2.57	\$ 8,728
			MULCHING										
323			3" D Hardwood Bark Mulching	SF	4230	10%	4653	0.012	\$ 46.90	\$ 0.56	\$ 1.17	\$ 1.73	\$ 8,063
			MISC										
324			1/8" Steel Bed Edging W/Stakes Spaced @ 30" O.C	LF	684	10%	752	0.085	\$ 46.90	\$ 3.99	\$ 6.95	\$ 10.94	\$ 8,229
												SUBTOTAL \$	40,609
												PROJECTED COST	
												OVERHEAD AND PROFIT	\$1,106,874
												15%	\$166,031
												INSURANCE	\$16,603
												2%	\$0
												CONTINGENCY	\$0
												0%	\$49,809
												TAX	\$49,809
												4.5%	\$1,339,317
												SUGGESTED BID	